PLANT SCHEDULE

	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL		P.U. OF V.C.1.a. EXTERNAL R.O.W.	P.U. OF V.C.1.a. INTERNAL R.O.W.	P.U. OF V.C.1.b. MD ROUTE 140	P.U. OF V.C.1.b. MALCOLM ROAD	P.U. OF V.C.1.c. PARKING LOT	P.U. OF V.C.1.e. DUMPSTER SCREENING	P.U. OF V.C.1.e. TRANSFORMER SCREENING	P.U. OF V.C.1.e. GAS AREA SCREENING	P.U. OF V.C.1.e. UNLOADING AREA SCREENING
TREES															
	PY	3	PRUNUS X YEDOENSIS / YOSHINO CHERRY (MINOR TREE) MIN 8' HT	B & B	2"CAL		--	--	--	3 / 2 = 1.5	--	--	--	--	--
	QP	10	QUERCUS PALUSTRIS / PIN OAK (MAJOR TREE) MIN 10' HT	B & B	2"CAL		3	--	--	--	7	--	--	--	--
EXISTING TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	CAL										
	EMA	16	EXISTING TREE (MAJOR)	EXISTING			2	8	2	--	1	--	--	--	--
	EMI	5	EXISTING TREE (MINOR)	EXISTING			1 / 2 = 0.5	--	4 / 2 = 2	--	--	--	--	--	--
SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	SIZE (HT)		SPACING									
	CE	138	CEPHALOTAXUS HARRINGTONIA `DUKE GARDENS` / DUKE GARDENS PLUM YEW	30"		36" o.c.	84 / 5 = 16.8	--	--	--	--	--	--	5 / 5 = 1	--
	CA	28	CLETHRA ALNIFOLIA / SUMMERSWEET CLETHRA	24"		36" o.c.	--	--	--	--	--	--	--	--	--
	IG	95	ILEX GLABRA `COMPACTA` / INKBERRY HOLLY	24"		36" o.c.	--	--	--	--	--	--	--	--	--
	PO	205	PRUNUS LAUROCERASUS `OTTO LUYKEN` / OTTO LUYKEN LAUREL	30"		36" o.c.	--	15 / 5 = 3	30 / 5 = 6	90 / 5 = 18	--	22 / 5 = 4.4	18 / 5 = 3	--	27 / 5 = 5.4
EXISTING	CODE	QTY	BOTANICAL / COMMON NAME	SIZE		SPACING									
	ES	32	EXISTING SHRUB TO BE MAINTAINED AT 36" HT	EXISTING		36" o.c.	2 / 5 = 0.4	--	30 / 5 = 6	--	--	--	--	--	--
GROUND COVERS	CODE	QTY	BOTANICAL / COMMON NAME	CONT		SPACING									
	CO	312	COREOPSIS GRANDIFLORA `EARLY SUNRISE` / LARGEFLOWER TICKSEED	4"POT		12" o.c.	300 SF / 250 = 1.2	--	--	--	--	--	--	--	--
	LS	606	LIRIOPE SPICATA / CREEPING LILY TURF	4"POT		10" o.c.	140 SF / 250 = 0.6	--	--	--	--	--	--	--	--
SOD/SEED	CODE	QTY	BOTANICAL / COMMON NAME	CONT		SPACING	TOTAL: 24.5 P.U.	TOTAL: 11 P.U.	TOTAL: 16 P.U.	TOTAL: 19.5 P.U.	TOTAL: 8 MAJOR TREES	TOTAL: 4.4 P.U.	TOTAL: 3 P.U.	TOTAL: 1 P.U.	TOTAL: 5.4 P.U.
	SEED	563 SF	SEEDING												
	SOD	4,484 SF	SOD TO MATCH EXISTING	SOD											

CITY OF WESTMINSTER LANDSCAPE NOTES:

1. LANDSCAPE SPECIFICATIONS SHALL CONFORM TO THE CURRENT LANDSCAPE SPECIFICATIONS GUIDELINES BY LANDSCAPE CONTRACTORS ASSOCIATION, MD-DC-VA. ALL NURSERY STOCK SHALL BE PLANTED IN ACCORDANCE WITH THE PROCEDURES OUTLINED IN THE GUIDELINES WITH THE FOLLOWING EXCEPTIONS:
   - 1.1. IF THE SOIL IS WET OR COMPACTED, ALL CONTAINERIZED AND BALLED NURSERY STOCK SHOULD BE PLANTED IN SUCH THAT THE TOP ONE-THIRD OF THE ROOTBALL IS ABOVE THE EXISTING GRADE. THIS DEPARTURE IN THE ESTABLISHED PROCEDURES HAS BEEN DOCUMENTED TO INCREASE THE RATE OF TRANSPLANTED SUCCESS IN THESE TYPES OF SOILS.
   - 1.2. WIRE AND NONDEGRADABLE MATERIALS SHOULD BE REMOVED AS FAR AS PRACTICAL BEFORE BACKFILLING TO PREVENT ROOT GIRDLING.
2. ALL NURSERY STOCK SHALL BE NURSERY GROWN AND SHALL CONFORM TO AMERICAN ASSOCIATION OF NURSERYMEN, INC. STANDARDS.
3. ALL PLANTING PROCEDURES AND SPECIFICATIONS SHALL CONFORM TO A LANDSCAPE SPECIFICATION GUIDELINES FOR BALTIMORE-WASHINGTON METROPOLITAN AREAS, @ LATEST EDITION.

PLAN PREPARATION AND CERTIFICATION NOTE:

SEE PLAN PREPARATION AND CERTIFICATION ON SHEET L-2.

CONTRACTOR NOTE:

CONTRACTOR TO MAINTAIN LANDSCAPING FOR 90 DAYS AFTER CERTIFICATE OF OCCUPANCY.

PROPERTY INFO:

PLAT BOOK NO. 42, FOLIO 9

AREA OF DISTURBANCE: 1.3 ACRES

PROJECT DIRECTORY

LAND OWNER / DEVELOPER
CFT NV DEVELOPMENTS, LLC
1683 WALNUT GROVE AVE
ROSEMEAD, CA 91770
626-372-8122
CONTACT: CHARLIE SHEN

LANDSCAPE ARCHITECT
FORESITE GROUP, LLC.
3740 DAVINCI CT, SUITE 100
PEACHTREE CORNERS, GA 30092
(770) 368-1399
CONTACT: JASON WECKERLY

ARCHITECT / APPLICANT
NORR
150 W JEFFERSON AVE, SUITE 1300
DETROIT, MI 48226
313-324-3129
CONTACT: VALENTINO MANCINI


SITE
Baltimore Blvd
Malcolm Dr
Old Westminster Rd
Old Taneytown Rd
Malcolm Dr.
Hidden Valley
Wilson Village
Old Farm Lane
Hidden Ln
Wilson Ln
Wilson Ln.
Wilson Ln.
Wilson Ln.